

Plant Schedule						
Trees						
Number	Abbreviation	Species	Girth	Height	Specification	
1	Be pe	Betula pendula	16-18cm	400-450cm	Extra Heavy Standard: 3x RB: Clear Stem min. 200cm	
3	Ma sy	Malus sylvestris	6-8cm	250-300cm	Light Standard: 3 brks: 2x RB: Clear Stem 150-175cm	
6	Ma Co	Cox's Orange Pippin (Malus domestica 'Cox's Orange Pippin')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm	
4	Md Bs	Bramley's Seedling (Malus domestica 'Bramley's Seedling')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm	
5	Md d	Dabinett (Malus domestica 'Dabinett')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm	
6	Py Co	Conference (Pyrus communis 'Conference')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm	
4	Py Bo	Williams' Bon Chrétien (Pyrus communis 'Williams' Bon Chrétien')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm	
3	Pr Vi	Victoria (Prunus domestica 'Victoria')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x RB: Clear stem 150-175 cm	
4	Pr Da	Damson (Prunus domestica 'Damson')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x RB: Clear stem 150-175 cm	
4	Pr Mo	Morello (Prunus cerasus 'Morello')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x RB: Clear stem 150-175 cm	
4	Pr St	Stella (Prunus avium 'Stella')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x RB: Clear stem 150-175 cm	
Total		44				
Ornamental Hedge						
Number	Abbreviation	Species	Height	Pot Size	Specification	Density
17	Pr ol	Prunus laurocerasus 'Otto Luyken'	40-60cm	5-7.5L	Bushy: 5 brks: C	0.7Ctr
Total		17				
Native Hedgerow						
Number	Abbreviation	Species	Height	Density	Specification	
91	Co Av	Hazel (Corylus avellana)	80-100cm	15/10m	1+1: Transplant - seed raised: B	
242	Cr Mo	Hawthorn (Crataegus monogyna)	80-100cm	4/m	1+2: Transplant - seed raised: B	
61	Cr mo	Ash (Fraxinus excelsior)	80-100cm	1/m	1+2: Transplant - seed raised: B	
91	Pr sp	Prunus spinosa	80-100cm	15/10m	1+2: Transplant - seed raised: B	
121	Ro ca	Field Maple (Acer campestre)	80-100cm	2/m	1+2: Transplant - seed raised: B	
Total		606				
Translocated hedge -51m2						

KEY:

- EXISTING HEDGE (2m height)
- TRANSLOCATED HEDGE (Maintained to 2m in height)
- NEW HEDGE PLANTED
- HEDGE TO BE REMOVED
- SPECIES RICH GRASS SEED MIX
- NATIVE WILDFLOWER SEED MIX



x4no. Ash trees planted in trench for relocated hedge

51m2 Translocated hedge Maintained to 2m in height

Berm created with soil from stable excavations to screen appearance of patio from the South/ East. Soil to be seeded with grass/ wildflower mix.

130 linear meters of native hedgrow to be planted along historic field boundary to restore historic field pattern in landscape

Historic Orchard replanted as per planting schedule

Site: Land North of Rock Cottage NP26 3AJ

Drawing No. TG2203-25

Project No. TG2203

Drawn. -



Ty Green Ltd.
 Tel: 07427657573
 spence@tygreen.co.uk
 www.tygreen.co.uk
 Cefn Llogell Farm, Newport, NP10 8TR



Title: Soft landscaping plan

Scale at A2 1:200

Date June 2024

Revision. -