



FRONT ELEVATION

SIDE ELEVATION

- EXTERNAL MATERIAL FINISHES SCHEDULE:**
- ① Facing brickwork to main walls. Colour red as approved.
  - ② Roof Tiles. Quality replica slate.
  - ③ Cast stone sills. Colour to be confirmed.
  - ④ Hardwood Timber windows. Colour to be confirmed.
  - ⑤ PPC aluminium windows, screens and bi-fold doors. Colour to be confirmed.
  - ⑥ Upvc fascias and soffits. Colour to be confirmed.
  - ⑦ Upvc Rainwater Goods. Colour to be confirmed.
  - ⑧ Cast stone window / door heads & string course. Colour to be confirmed.
  - ⑨ Render. Parex Roughcast Render. Colour to be confirmed.
  - ⑩ Wall Tile Hanging. Colour Red / Brindle to be confirmed



REAR ELEVATION

SIDE ELEVATION

Status: **PLANNING**

rev	date	description
A	18/06/19	Changed external finish to render
B	09/07/25	Client name amended

This drawing is copyright and its use or reproduction without the permission of Spring Design Consultancy Limited. All rights are reserved until invoices are paid in full. No responsibility will be taken for any design used for construction prior to receipt of relevant approvals.

by	Drawn:	MN	Client:	Harmoni Homes
MN	Checked:	CTW	Project:	Chepstow Road, Langstone
	Date:	Jan 2019	Title:	House Type 1890 Elevations
	Scale:	1:100 @ A3	Ref:	2342 - 204
			Rev:	B



Unit 3 Chapel Barns | Merthyr Mawr  
 Bridgend | CF32 0LS | 01656 656267  
 mail@spring-consultancy.co.uk