Plant Schedule

Trees

Number	Abbreviation	Species	Girth	Height	Specification
1	Be pe	Betula pendula	16-18cm	400-450cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
3	Ma sy	Malus sylvestris	6-8cm	250-300cm	Light Standard: 3 brks: 2x: RB: Clear Stem 150-175cm
6	Ma Co	Cox's Orange Pippin (Malus domestica 'Cox's Orange Pippin')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm
4	Md Bs	Bramley's Seedling (Malus domestica 'Bramley's Seedling')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm
5	Md d	Dabinett (Malus domestica 'Dabinett')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm
6	Py Co	Conference (Pyrus communis 'Conference')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm
4	Py Bo	Williams' Bon Chrétien (Pyrus communis 'Williams' Bon Chrétien')	12-14cm	350-400cm	Extra Heavy Standard: 3x RB: Clear stem min. 200 cm
3	Pr Vi	Victoria (Prunus domestica 'Victoria')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x: RB: Clear stem 150-175 cm
4	Pr Da	Damson (Prunus domestica 'Damson')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x: RB: Clear stem 150-175 cm
4	Pr Mo	Morello (Prunus cerasus 'Morello')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x: RB: Clear stem 150-175 cm
4	Pr St	Stella (Prunus avium 'Stella')	6-8cm	250-300cm	Light Standard: 3 Brks: 2x: RB: Clear stem 150-175 cm
Total	**44**				

Ornamental Hedge

Number	Abbreviation	Species	Height	Pot Size	Specification	Density
135	Fa Sy	Fagus sylvatica	60-80 cm	Bareroot	Bushy: 5 brks: C	30cm Ctrs
Total	105					

Native Hedgerow

Number	Abbreviation	Species	Height	Density	Specification
91	Co Av	Hazel (Corylus avellana)	80-100cm	15/10m	1+1: Transplant - seed raised: B
242	Cr Mo	Hawthorn (Crataegus monogyna)	80-100cm	4/m	1+2: Transplant - seed raised: B
61	Cr mo	Ash (Fraxinus excelsior)	80-100cm	1/m	1+2: Transplant - seed raised: B
91	Pr sp	Prunus spinosa	80-100cm	15/10m	1+2: Transplant - seed raised: B
121	Ro ca	Field Maple (Acer campestre)	80-100cm	2/m	1+2: Transplant - seed raised: B
Total	**606**				

341350E

KEY:
- EXISTING HEDGE (2m height)
- TRANSLOCATED HEDGE (Maintained to 2m in height)
- NEW HEDGE PLANTED
- HEDGE TO BE REMOVED
- SPECIES RICH EMORSGATE EM2 LAWN SEED MIX
- NATIVE WILDFLOWER SEED MIX
- NEW ORNAMENTAL HEDGE

x4no. Ash trees planted in trench for relocated hedge

Field

Translocated hedge -51m2

re Oak

2

A

75m2

CEZ

Vet Ash HF2+

T1

A

CEZ

CEZ

51m2 Translocated hedge
Maintained to 2m in height

1no. Be pe

1no. Ma sy

53 no. Fa Sy

2no. Ma sy

Barn

Md Co

Md d

Md Bs

52 no. Fa Sy

Bat House

Stables

Ma Co

Py Co

Md d

Py Bo

Drainage field

Pr Da

Pr Vi

Pr St

Pr Mo

Root proection fence

Post and rail fence defining boundry between high/low intensity managed grass

Berm created with soil from stable excavations to screen appearance of patio from the South/ East. Soil to be seeded with grass/ wildflower mix.

130 linear meters of native hedgrow to be planted along historic field boundary to restore historic field pattern in landscape

24m2 Translocated hedge
Maintained to 2m in height

Historic Orchard replanted as per planting schedule

Compost frame for grass cuttings

hedge ht 2.0m

asphalt road

overh

Site: Land North of Rock Cottage NP26 3AJ	**Drawing No.** TG2203-25	**Project No.** TG2203	**Drawn.** -	**Tŷ Green Ltd.** Tel: 07427657573 spence@tygreen.co.uk www.tygreen.co.uk Cefn Llogell Farm, Newport, NP10 8TR
Title: Soft landscaping plan	**Scale at A2** 1:200	**Date** Sep 2024	**Revision.** C	N