This 'As Built' drawing has been produced based on information provided by Norwest Holst Construction Ltd

DO NOT SCALE

FOR CONTINUATION SEE DRAWING 5041855 / LA / 4927

FOR LEVELS INFORMATION TO CHARNWOOD UNDERPASS FOOTPATH REFER TO HIGHWAYS ENGINEER'S DRAWINGS

REFER TO DRAWING 4933 FOR STEPS DETAILS

MUGA TO SPECIALIST SUBCONTRACTOR'S DETAILS

Raised log planters with secure water point

5m Diameter covered outdoor classroom with minimum 1500mm level surround

MAXIMUM HEIGHT TO 2.5m

Asphalt to hardplay: 240mm construction make-up

Rubberised play surface to manufacturer's specification

Slab paving to hardplay: 240mm construction make-up

Slab paving: 240mm construction make-up

Asphalt to main drive: 500mm construction make-up

Parking Bays: 280mm construction make-up

Resin Bound Gravel: 175mm construction make-up

ATP: 220mm construction make-up

Asphalt to hardplay: 240mm construction make-up

Slab paving to hardplay: 240mm construction make-up

Asphalt to main drive: 500mm construction make-up

Parking Bays: 280mm construction make-up

ATKINS

NOTES:

1. Refer to setting out plan for co-ordinate information, drawings 5041855/LA/4918 and 4919

2. Levels information has been developed from the capping layer levels information, drawing NHL1.02.TS5 001. Levels have been calculated to allow for full depth of construction make up above capping layer except where agreed with Norwest Holst. For construction make up of hard surfaced refer to to drawings 5041855/LA/4903 and 4904. For topsoil depth refer to drawing 5041855/LA/4917.

EXTERNAL LEVELS KEY

+ (10.000)	Existing Level
+ 10.000	Proposed Level
BOK	Bottom of Kerb Standard kerb height 125mm, refer to drawing 5041855/LA/4905 for kerb details
TOK	Top of Kerb
BOW	Bottom of Wall
TOW	Top of Wall
PL	Pitch Level
GL	Gully
FFL	Finished Floor Level
1:60	Gradient
CP	Contractor Provided Level Information Levels to Bottom of Kerb

Rev	Description	By	Date	Chkd	Auth
D	AS BUILT ISSUE	AL	28/10/08	NR	NR
B	Levels amended to drainage requirements	AD	10/12/08	SB	NR
A	Levels to car park and hardplay/ATP/MUGA updated as per agreement with Norwest Holst	AL	05/12/08	MD	MD

Rev	Purpose of issue	Date	Authorised
D	AS BUILT	28/10/08	NR
C	PLANNING	29/05/09	NR
B	CONSTRUCTION	10/12/08	NR
A	CONSTRUCTION	05/12/08	MD
O	COMMENT & REVIEW	01/12/08	COMMENT

VINCI

NORWEST HOLST

WS Atkins Consultants Limited ©
Design, Environment & Engineering
160 Aztec West, Almondsbury, Bristol. BS32 4TU.
Tel. 01454 201400 / Fax. 01454 201568

Project
Glebelands Development
St Julians
Newport

Title
Glan Usk School
AS BUILT
External Levels Plan 1 of 2

Original Scale	Drawn	Checked	Authorised
1:200	AHL	MD	MD
	Date 01/12/08	Date 05/12/08	Date 05/12/08

A0

Drawing Number 5041855 / LA / 4926

Rev D

Millimetres 0 10 150

A1

Job | Dept. | Sub | Unique No.

R.H.Box for client signatures when required

Complete to show purpose of each issue

Main section | Sub section | Detail | Initial issue signatures | Drg. No. & Latest Revision