

Important Note:

Existing cementitious render to front elevations to be carefully removed / hacked off & any defective / loose areas of existing masonry to external walls must be reported **IMMEDIATELY** to the Contract Administrator. All cementitious render removal works must halt on site until further instructions are provided by the Contract Administrator & Structural Engineer.

All existing feature stonework banding, detailing & window / door surrounds on front elevations must be retained.

Following exposure of existing stonework, condition of existing stonework will be inspected by the Contract Administrator & any remedial works will be instructed. Main Contractor to ensure records of all existing feature stonework details are logged & safely stored to maintain the existing appearance upon completion of proposed refurbishment works.

