

1. This drawing is to be read in conjunction with all other relevant Engineering and Architect's details.
2. All dimensions are in metres unless otherwise stated.
3. The Contractor shall be responsible for checking all tie-ins for line and level with existing foul and surface water systems before commencing any works.
4. The Engineer shall be notified immediately, in writing, should any errors or discrepancies be found prior to the commencement or continuation of any works.
5. All work is to be carried out in accordance with current British Standards, Building Regulations.
6. All drainage work is to be strictly in accordance with the requirements of the Building Regulations 2015, Approved Document Part H, "Drainage and waste disposal".
7. It is the responsibility of the Contractor to execute the works at all times in strict accordance with the requirements of the Health and Safety at Work Act 1974, and the C.D.M. Regulations 2015. The Contractor shall be deemed to have allowed for full compliance, including full liaison with the Principle Designer, within his rates.
8. All existing land drains encountered on site during construction are to be re-connected.
9. Should any departure from the proposed slab or external levels be considered, agreement shall be sought from the Engineer immediately and prior to the commencement or continuation of any works. Proposals should take full account of all restrictions to the slab level.
10. Temporary protection to be provided to drainage work during construction as necessary.

 Water Monitoring Position
 Reen

 1. Working close to steep or difficult ground.

2. Working close to Reen.

	Used to provide design specific safety information that may not be obvious to a competent contractor but may be useful.
	Used to restrict/prevent a possible action, eg. stop construction traffic from entering an area.
	Used to warn of significant design hazards, adding recommendations
	Used to encourage a positive action, e.g. use of robust protection for inspection chambers



Copyright © Rodgers Leask Limited

