



FOOTPATH 402/5/1

6.0M LONG PORTION OF DRIVE TO
HAVE TARMAC FINISH

THIS SECTION OF THE HEDGE
IS TO BE TRANSLOCATED BEHIND VIS SPLAY

1.8M HIGH METAL MESH FENCE
AND GATES.
(See photo example)

INSTALL A BAT BOX IN THIS TREE
AT LEAST 4.0M HIGH

INSTALL BIRD BOX
IN STABLE GABLE

STONE FINISH DRIVE

STONE FINISH
TURNING AREA

Drive construction to be :-
Gravel finish, on stone base
on 1000g Terram.

A 28.01.25 Various notes added.

Revision	Date	Description
A	28.01.25	Various notes added.

This drawing is the property of CJ Projects and the drawing is issued on the condition
That it is not copied, reproduced, retained or disclosed to any unauthorised person,
either wholly or in part, without the consent in writing of CJ Projects.

All dimensions are to be verified on site.

Project **Retention of Vehicle Access**
Homeland, Penhow, Newport. NP26 3AJ

Title **PROPOSED SITE PLAN**

Client **Mr M THOMAS**

Scale **1:500@A4**

Date **DEC 24**

Drawing No. **2451/03A**

CJ PROJECTS
Architectural Services

Oaklands, Devauden, Chepstow, Monmouthshire. NP16 6PE
07779 011828 chris.j@cjprojects.co.uk

Homeland