

Existing secondary steel posts retained and finished to match window frame colour.

Vertical fin bries soleil. Outer frame to match colour of windows. Fins to contrast in colour with outer frame.

Tinted, solar control glazing

Existing secondary steel posts retained and finished to match window frame colour.

Existing brickwork retained as existing

Existing concrete edge beam repaired as required and painted white.

Existing glazed top lights removed and replaced with new frames in-filled with solid panels or louvre to suit use.

Existing head beam retained and pre-finished panel applied. Colour to match window frames.

Smart Systems fixed light aluminium window behind bries soleil. Colour RAL 7012

Smart Systems VS600 sash window to be restricted to 100mm max. opening (top and/or bottom) without 2 stage override. Colour RAL 7012



Typical window - Proposed

1 : 25

This drawing must not be scaled.
Figured dimensions, levels, etc. only are to be used.
Any inaccuracies, etc. must be notified to the Project Supervisor. This drawing is copyright detail drawings and larger scale drawings take precedence over smaller scale drawings.

GENERAL NOTES

REVISIONS

Rev	Date	Description	By
C	16.09.25	Issued for planning	NH
B	01.08.25	Updated and issued for pre-app	NH
	29.04.25	Issued for estimates	NH



Works & Estates Management Centre
St. Cadocs Hospital
Lodge Road
Caerleon
NP18 3XQ

PROJECT TITLE
Royal Gwent Hospital
Cardiff Road, Newport
Replacement of B Block windows

DRAWING TITLE
Proposed replacement window type

DRAWN BY NH CHK BY

PROJECT REF RGH B SCALE 1 : 25
original paper size of A2

REVISION C DATE 16.09.25

STATUS PL SUITABILITY Issued for Planning Approval

Project	Originator	Volume	Level	Type	Role	Number
RGH B	ABUHB	XX	XXX	DT	A	100