DO NOT SCALE

This 'As Built' drawing has been produced based on information provided by Norwest Holst Construction Ltd

6 No. Sorbus aucuparia 'Sheerwater Seedling' @ 5000mm c/s grid

3 No. Malus 'Rudolf' @ 5000mm c/s grid

6 No. Malus 'Golden Hornet' @ 5000mm c/s grid

6 No. Prunus avium @ 5000mm c/s grid

3 No. Corylus avellana @ 5000mm c/s grid

FOR CONTINUATION SEE DRAWING 5041855 / LA / 4906

Raised log planters with secure water point

8 No. Prunus cerasus 'Morello'

2 No. Carpinus betula

~~100 No.~~ Lonicera nitida 'May Green' @ 500mm c/s

3 No. Carpinus betula planted in structural tree soil

185 No. Salvia officinalis @ 450mm c/s

245 No. Hebe albican @ 500mm c/s

115 No. Ceanothus 'Blue Mound' @ 750mm c/s

70 No. Choisya ternata @ 750mm c/s

4 No. Fraxinus excelsior planted in structural tree soil

64 No. Salix rosmarinifolia @ 750mm c/s

45 No. Cornus stolonifera 'Flaviramea' @ 1000mm c/s

190 No. Festuca Glauca @ 500mm c/s

120 No. Lonicera nitida 'May Green' @ 500mm c/s

DROP OFF ONLY

IN

OUT

2 No. Carpinus betula planted in structural tree soil

2 No. Carpinus betula

65 No. Lonicera nitida 'May Green' @ 500mm c/s

4 No. Betula utilis Jacquemontii

65 No. Mentha x gentilis 'Variegata' @ 450mm c/s

70 No. Thymus carnosus @ 450mm c/s

80 No. Lavandula angustifolia 'Hidcote' @ 450mm c/s

40 No. Cornus alba 'Sibirica' @ 1000mm c/s

Timber edged planting bed for school use

40 No. Cornus stolonifera 'Flaviramea' @ 750mm c/s

80 No. Cotinus x dummerii 'Grace' @ 750mm c/s

92 No. Cotoneaster simonsii @ 750mm c/s

Area to be regraded using suitable soil / fill material to form a level surface, topsoiled to a depth of 150mm and seeded with amenity grass seed as per request by NCC Parks Department.

Drop kerb for maintenance vehicle access

Area to be left tidy on completion of works

Existing planting to be brought under maintenance and reduced in height as per request by Authority

Playground

St Julian's Glebelands
(Recreation Ground)

0 10 Millimetres 150

A0

ATKINS

REFER TO DRAWING 5041855 / LA / 4908 FOR PLANTING SCHEDULE AND DETAILS

Planting Key

- Ornamental Shrubs
- Specimen Shrubs
- Specimen Trees
- Native Hedgerow
- Native Planting Mix
- Hay and Wildflower Meadow
- Informal Soft Play and Sports Pitches
- Deterent Ground Cover

Aquatic Planting

- Marginal Planting
- Oxygenating Planting

Rev	Description	By	Date	Chk'd	Auth
G	AS BUILT ISSUE	AL	29/10/08	NR	NR
F	Treatment to area outside main entrance amended as per agreement with NCC Parks Department, planting omitted from car park island	AL	25/08/08	MD	MD
D	Orchard tree species amended as per the Client's rquirements	AL	19/03/08	NR	NR
C	Issued for planning approval of revised planting species and densities	AL	06/03/08	MD	MD
B	Planting densities to shrub beds reduced in accordance with contractor's requirements	AL	22/12/06	MD	MD

Rev	Purpose of issue	Date	Authorised
G	AS BUILT	29/10/08	NR
F	CONSTRUCTION	25/08/08	MD
E	PLANNING	29/05/08	NR
D	CONSTRUCTION	19/03/08	NR
C	PLANNING	06/03/08	MD
B	CONSTRUCTION	22/12/08	MD
A	CONSTRUCTION	08/10/08	AC

VINCI

NORWEST HOLST

WS Atkins Consultants Limited ©
Design, Environment & Engineering
160 Aztec West, Almondsbury, Bristol. BS32 4TU.
Tel: 01454 201400 / Fax: 01454 201568

Project
Glebelands Development
St Julians
Newport

Title
Glan Usk School
AS BUILT
Planting Plan Sheet 2 of 2

Original Scale	Drawn	Checked	Authorised
1:200	AHL	NR	NR
	Date 08/10/08	Date 06/10/08	Date 08/10/08

Drawing Number: 5041855 / LA / 4907 — Rev: G

Job / Dept. / Sub / Unique No.

R.H.Box for client signatures when required

Complete to show purpose of each issue

Main section

Sub section

Detail

Initial issue signatures

Drg. No. & Latest Revision